



Hennepin County Transportation Department

ADDENDUM

**TO PLANS, SPECIFICATIONS AND SPECIAL PROVISIONS FOR
CSAH 101 FROM CSAH 62 TO HUTCHINS DRIVE
HENNEPIN COUNTY TRANSPORTATION DEPARTMENT**

(To be opened Tuesday, February 17, 2015 at 2:00 P.M.)

ADDENDUM NO. 5

**CSAH 101; C.P. 9917
S.A.P. 027-701-019; 027-603-057**

NOTICE TO ALL BIDDERS:

PROPOSAL

1. **Replace** Division SS with Attachment A – Division SS.
2. Division S-110 (2575) SELECT TOPSOIL BORROW (SPECIAL), **Replace** the section heading on page 185-S to (2574) SELECT TOPSOIL BORROW (SPECIAL).

Replace paragraph A on page 185-S with the following:

Mn/DOT Standard Specification 2105 with the following modifications shall govern the work of this Section described as Item 2574.607.

Replace paragraph D on page 185-S with the following:

D. Measurement will be on a Plan Quantity basis. Payment at the Contract unit price per CUBIC YARD for Item 2574.607, Select Topsoil Borrow (Special) CV shall be compensation in full for all costs to excavate borrow locations, dispose of excavated materials and furnish and place the specified material as described in these Special Provisions, detailed in the Plans and as directed by the Engineer. The provisions of Mn/DOT 1903 shall not apply to item 2574.607, Select Topsoil Borrow (Special) CV.

Replace the second paragraph of section S-110.1.B on page 185-S with the following:

This topsoil borrow item has been included to replace the topsoil which had previously existed in turf areas along City streets. Existing topsoil that is stripped shall not be re-used in turf establishment (top 6 inches) unless specifically approved by the Engineer in the field. Any excavated topsoil may be used as common material in yard and boulevard areas.

3. Division SSW (2506) MANHOLES AND CATCH BASINS, **replace** the last paragraph on page 25 of 31, Seal Manhole, with the following:

Seal Manhole - Sanitary manholes to be sealed shall include removal and replacement of the casting and removal of the adjusting rings, furnishing and installing new adjusting rings, **furnishing and installing chimney seals**, thoroughly cleaning the existing structure, removal and replacement of grout on the dog house, inverts, and structure wall to the satisfaction of the Engineer. Structure walls where infiltration is evident shall be sealed using the chemical grout process. Upon completion of cleaning and sealing as required, the structure walls shall be spray lined with Quadex Dynastone or approved equal. Application of the spray liner shall be in accordance with the manufacturer's specifications. This work shall be completed after all sanitary sewer repair/replacement work has been completed and the final casting adjustment has been made. Structure walls where infiltration is evident shall be sealed using the chemical grout process.

4. Division SSW (2506) MANHOLES AND CATCH BASINS, **replace** the second paragraph on page 28 of 31, Item 2506.602 Seal Manhole, with the following:

Item 2506.602 Seal Manhole: Payment shall by the each and the unit bid price shall include all labor, equipment, materials, all removals, reinstallations of castings, furnishing and installing adjusting rings, **furnishing and installing new chimney seals**, cleaning of the existing structure, removal and replacement of grout as specified above, chemical grout sealing, and interior spray-on liner. Manholes depths vary.

5. **Add** Section 01569 Temporary Conveyance of Wastewater to the Metropolitan Council specifications with Attachment B.

PLANS

See Attachment C - Revised Plan Sheets for the following modifications:

1. Plan Sheet No. 10R ESTIMATED QUANTITIES – **Remove and Replace** with attached Sheet 10R1. 2575.607 SELECT TOPSOIL BORROW (SPECIAL) CV item changed to 2574.607 SELECT TOPSOIL BORROW (SPECIAL) CV. Quantities updated.
2. Plan Sheet No. 416 SIGNAL PLAN – **Remove and Replace** with attached Sheet 416R. Original Note 1 deleted. Original note 2 becomes note 1. Standard plate 8114A removed from list.
3. Plan Sheet No. 418 SIGNAL PLAN – **Remove and Replace** with attached Sheet 418R. Wiring diagram updated to new Hennepin County detail.
4. Plan Sheet No. 419 TRAFFIC CONTROL SIGNAL SYSTEM “B” – CABINET DETAIL – **Remove and Replace** with attached Sheet 419R. Extra 2 inch RSC added.
5. Plan Sheet No. 420 TRAFFIC CONTROL SIGNAL SYSTEM “C” – CABINET DETAIL – **Remove and Replace** with attached Sheet 420R. Extra 2 inch RSC added.
6. Plan Sheet No. 423 TRAFFIC CONTROL SIGNAL SYSTEM – TEMPORARY SIGNAL SYSTEM – **Remove and Replace** with attached Sheet 423R. Text deleted regarding placement of signal heads in upper left detail.
7. Plan Sheet No. 428 TRAFFIC CONTROL SIGNAL TEMPORARY SYSTEM “B” – CSAH 101 @ HANUS RD – **Remove and Replace** with attached Sheet 428R. Notes 2 and 8 revised. Note 11 added.
8. Plan Sheet No. 436 TRAFFIC CONTROL SIGNAL TEMPORARY SYSTEM “C” – CSAH 101 @ CSAH 3 – **Remove and Replace** with attached Sheet 436R. Notes 2 and 8 revised. SOP callout added to layout.

ELECTRONIC BID FORM

1. The following quantities are hereby revised in the Electronic Bid Form:

<u>Item No.</u>	<u>Item Description</u>	<u>Units</u>	<u>Quantity (Previous Qty)</u>
2574.607	SELECT TOPSOIL BORROW (SPECIAL) CV	CU YD	3266 (580)

KSA
February 12, 2015
Attachment(s)

Receipt of this addendum must be acknowledged in accordance with the provisions of 1210 of the specifications.

Attachment A – Division SS

Attachment B – Section 01569 Temporary Conveyance of Wastewater

Attachment C – Revised Plan Sheets